

Notice inviting E-Tender
Rabindra Bharati University
56 A, B T Road, Kolkata-50
RB/REG/ 934 /2021 dated 19.2.2021

E Tenders are invited for civil works at Emerald Brower Campus from reputed civil contractors (having experience in carrying out works in educational institution with minimum annual turnover of 10 lacs rupees single job) with current trade license, current P Tax challan, GST registered certificate, PAN Card, last 3 yrs IT returns, last 3 yrs audit, profit & loss balance sheet, copy of EMD of rupees forty thousand only purchased, credential of works mentioned above as desired within two weeks from the date of tender for the works mentioned in government tender portal. The decision of the University regarding selection will be final and binding on all tenderers.

Description: Construction of shed with steel and fibre glass and ancillary works on northern side of Ramanujam Bhawan near finance Department at EB Campus

Registrar

Sl No	Description of work	Estimated Value	EMD amount	Essential Credential	Time allotted	Other conditions
7	Construction of shed with steel structures and ancillary works in front of Finance and cash at EB Campus	1869995/-	Rs 40000.00	Credential for steel and civil works for Rs 10 lacs single work	2.5 months	-Do-

Name of the Work : Steel Structural shed beside Finance Department over R.C.C. Column

Sl. No.	Description of Item	unit	Rate	Qty	Amount
1	125 mm. thick brick work with 1st class bricks in cement mortar (1:4) in ground floor.	sqm	736.00	9.65	7102.40
2	Artificial stone in floor, dado, staircase etc with cement concrete (1:2:4) with stone chips, laid in panels as directed with topping made with ordinary or white cement (as necessary) and marble dust in proportion (1:2) including smooth finishing and rounding off corners including raking out joints or roughening of concrete surface and application of cement slurry before flooring works using cement @ 1.75 kg/sq.m all complete including all materials and labour. In ground floor. 3 mm. thick topping (High polishing grinding on this item is not permitted with ordinary cement). Using grey cement	sqm	337.00	185.39	62476.43
3	Extra cost of labour over grey artificial stone for (i) Chequering	sqm	15.00	185.39	2780.85
4	Supplying dividing strip fitted and fixed with cement mortar (1:3) in mosaic or patent stone floor, dado etc. complete as per direction of the Engineer-in-charge. (ii) Aluminium - 25 mm. wide & 2mm. thick.	Mtr	43.00	35.50	1526.50
5	Supplying, fitting and fixing glass reinforced polyester translucent fiber sheet 300mm wide in half round gutter in roof as per IS: 12866 - 1989 fitted and fixed with 50 X 6mm MS Clamp with necessary bolts and nuts, screws and jointing material complete as per direction of Engineer - in - Charge. a) 1.6mm +/- 0.2 mm thick sheet. i) Natural white or tinted blue colour	Mtr	783.00	85.00	66555.00
7	Ordinary Cement concrete (mix 1:2:4) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement,if any, in ground floor as per relevant IS codes. a) Pakur Variety	Cum	5524.80	16.450	90882.96
8	M.S. works in brackets made from flats, angles, tees etc. to sizes specially bent, twisted, forged; making holes drilled and fitted torafter of trusses with necessary bolts, nuts, washer or screws etc.(length of straight not less than 230 mm)	Qtl.	9984.00	43.500	434304.00
9	Welding in M.S. structural work with gas or electric: (a) Tack weld	Point	9.00	16.450	148.05
	(a) Tack weld	cm Run	9.00	16.450	148.05

C/O Rs 665924.24

Sl. No.	Description of Item	unit	Rate	Qty	Amount
				B/F Rs	665924.24
10	Supplying, fitting and fixing glass reinforced polyester translucent fiber glass sheet to match with GCI Corrugation as per IS: 12866 - 1989 in roof fitted and fixed with 10 mm dia "J" or "L" hook, bolts and nuts, limpet and bitumen washers and putty with 150mm end lap and one corrugation minimum side lap complete. b) 2.0mm +/- 0.2 mm thick sheet (3.25 Kg/sqm) ii) Fire retardant milky white	sqm	959.00	260.000	249340.00
11	Holding down bolt with nut including 100 x 100 x 6 mm plate washer at bottom fitted complete and packing the hole with cement concrete or cement grout as directed. ii) 20mm dia bolt				
	a) 300 mm long	Each	141.00	88.000	12408.00
12	Labour for hoisting and placing in proper position (up to 1st floor level) departmental R.S. joists, channels, angles. Tees, plates etc. including fitting and fixing same with bolts and nuts, if necessary (but excluding cost of such bolts and nuts)				
		Qtl.	412.00	43.500	17922.00
13	Supplying, fitting and fixing PVC pipes of approved make of (medium duty) conforming to ASTM D - 1785 and threaded to match with GI Pipes as per IS : 1239 (Part - I). with all necessary accessories, specials viz. socket, bend, tee, union, cross, elbo, nipple, long screw, reducing socket, reducing tee, short piece etc. fitted with holder bats clamps, including cutting pipes, making threads, fitting, fixing etc. complete in all respect including cost of all necessary fittings as required, jointing materials and two coats of painting with approved paint in any position above ground. (Payment will be made on the centre line measurements of total pipe line including all specials. No separate payment will be made for accessories, specials. Payment for painting will be made separately) (a) For Exposed Work PVC Pipes 150mm				
		Mtr	1824.00	40.000	72960.00
6	Single Brick Flat Soling of picked jhama bricks including ramming and dressing bed to proper level and filling joints with local sand.	sqm	361.00	768.720	277507.92
7	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or concrete surface old or new surface to receive decorative textured (matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface thoroughly, complete as per manufacturer's specification and as per direction of the EIC. (b) Two Coats in Ground Floor	Sqm	45.10	768.720	34669.27
				C/O Rs	1330731.43

Sl. No.	Description of Item	unit	Rate	Qty	Amount
				B/F Rs	1330731.43
8	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety	Cum	6187.61	6.120	37868.17
9	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of EIC to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer. c) Super Protective 100% Acrylic Emulsion.	Sqm	97.00	768.720	74565.84
10	Red oxide wash of approved shade including cleaning and smoothening surface thoroughly (without specific permission from the Engineer-in-charge this item of work must not be done on an old painted surface which has not received such red oxide wash before) : External surface (Ground floor) (b) Two coats (on new works only).	Sqm	33.00	199.950	6598.35
11	A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary : (b) On steel or other metal surface : With super gloss (hi-gloss) - (iv) Two coats (with any shade except white)	sqm	79.00	199.950	15796.05
12	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints including throating, nosing and drip course, scaffolding/staging where necessary (Ground floor).[Excluding cost of chipping over concrete surface] (i) With 1:6 cement mortar (a) 25 mm thick plaster	sqm	205.00	765.500	156927.50
13	Extra for fluted, corrugated or ribbed plaster (over rate of corresponding rete of plaster) (Cement 0.135 cum/100 sq.m)	sqm	40.00	765.500	30620.00
				A Rs	1653107.34
	Add 6% CGST on A				99186.44
	Add 6% SGST on A				99186.44
					1851480.22
	Add 1% Labour Welfare Cess				18514.80
					1869995.40
				Say Rs	1869995/-

(Rupees Eighteen Lacs Sixty Nine Thousand Nine Hundred Ninty Five Only)